

A/18404/31/2005/DMS
Govt. of India
Delhi Milk Scheme
West Patel Nagar
New Delhi 110008

Name of work: - Cleaning of ETP & RWH tanks in DMS West Patel Nagar New Delhi
During 2017-18

Items rate sealed quotations are invited from the working/ willing contractors for the work mentioned above and same shall be received up to 2.30 PM and shall be opened at 3.00 PM on 24.05.2017 in the office of Assistant Engineer (Civil) in the presence of intending contractors. Contractors should satisfy themselves with the scope of work before quoting their rates. Quotationers are requested to send same by post or put in the tender box kept at reception hall at DMS West Patel Nagar New Delhi,

S.NO.	Detail of Items	Time for cleaning	Qty	Unit	Rate	Amount
1	Cleaning of the silted mud with other effluent material from the under mentioned tanks manually. The silted and other effluent material should be disposed off from the site within 5 days after cleaning of particular tank. After cleaning of RWH tanks a layer of coarse sand of 75 mm thick will be laid on tank area including digging of existing layer of stone aggregate .The work will be executed under the supervision of the Engineer/ Officer in charge					
	A. Sump house (approximate size 22'X12'X9')					
		20 days	one job	each	-----	-----
	B Equalization tank (app. Size 40'X40'X12')					
		20 days	two jobs	each	-----	-----
	C Blower tank					
		15days	one job	each	-----	-----
	D Sludge tank (app. size 20'X12'X9')					
		20days	one job	each	-----	-----
	E Treated water storage tank (app. Size 8'.6"X12'.0"X12'.0")					
		10 days	one job	each	-----	-----

