


NO.A/18403/14/DMS/2008

Dated 18.04.2013

In charge EDP (DMS) is requested to send the enclosed Notice Inviting Sealed Item Rate Quotation/Tender to CPP (Portal) as per office order NO.3-1/10-11/PUR/Misc., Store purchase section dated 28.12.2011 and NIC Krishi Bhawan New Delhi to publish/display the same on DMS Web site also. (dms.gov.in.tender.htm)


Balwan Singh
Assistant Engineer (Civil)

✓ Sh.Anuj Jain Accounts Officer
In charge, EDP (DMS)

Copy to:-

1 P.A. to DGM (T) for kind information of DGM (T)

65- AIL
25/4

NO. A/18403/14/DMS/2008
 Govt. of India
 Delhi Milk Scheme
 West Patel Nager New Delhi 110008

Sealed items rate quotations are invited for the work mentioned below and same shall be received from working/ willing contractors up to 2.30 P.M. and same shall be opened at 3.00 P.M. on 06.05.2013 in the office of Assistant Engineer (Civil) in the presence of indenting contractors. Quotationers should satisfy themselves with the scope of work before quoting their rates. Quotationers are requested to put the same in the tender box kept in the reception hall.

Subject :- Cleaning of sewer and storm water drains in DMS premises including DMS Colony shadipur during 2013-14

ABSTRACT OF COST

S.NO.	Description of items	qty.	unit	rate	amount
1	Cleaning of sewer lines and storm water drains including shadipur colony. Cleaning to be done by ropes, kharpatchies etc. and wherever line is blocked and cannot be opened manually, sewer line rodding machine is to be installed. All precautionary measures to avoid any accident during the course of cleaning shall be taken up by the contractors and arrangement for safety belts, first aid material or oxygen supply machine during the course of cleaning shall be made by the contractors at his own cost and on account of any accident nothing extra shall be paid to the contractor				
	a. 200 mm or below dia lines	2850.00	metre	-----	-----
	b. 200 mm or above dia lines	425.00	metre	-----	-----
2	Cleaning of storm water gully chamber and sewer lines manholes all sizes				
		295.0	Each	-----	-----
3.	Cleaning of open surface storm water drains running by side of road and wall, all size				
		1000.0	Metre	-----	-----
3	Disposal of silt earth by mechanical transport capacity not less than 6.00 cum including loading and unloading up to nearest dumping ground outside the DMS premises				
		7	each trip	-----	-----
				Total cost of work: - -----	

CONDITIONS :- AS ENCLOSED

