

NO. A/18402/04/DMS/2017-18
Govt. of India
Delhi Milk Scheme
West Patel Nager New Delhi 110008

Sealed percentage rate sealed quotations are invited for the work mentioned below and same shall be received from working/ willing contractors and registered with CPWD, MCD, NDMC, PWD etc. having GST number/.registration as per Govt. rules (GST July 2017) up to 2.30 P.M. and same shall be opened at 3.00 P.M. on 27.10.2017 in the office of Assistant Engineer (Civil) in the presence of indenting contractors. Quotationers should satisfy themselves with the scope of work before quoting their rates. Quotationers are requested to put the same in the tender box kept in the reception hall.

Subject: - Providing and fixing M.S. Door shutter on car garage No. -5 in DMS colony Shadipur during 2017-18

SCHEDULE OF WORKS/ITEMS

S.NO.	Description of items	qty.	unit	rate	amount
1.	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per direction of engineer in charge.	100.00	kg	73.95.00	7395/-
2.	Providing and fixing 1 mm thick M.S. Sheet door with frame of 40X40X6 mm angle iron and 3 mm M.S. gusset plates at the junction and corners all necessary fitting complete including applying a priming coat of approved steel primer.	7.00	sqm	3073.85	21517/-
3.	Providing and laying cement concrete in retaining walls ,returns walls, walls including attached pilasters , colomns ,piers, abutments ,string courses ,parapets etc. up to floor five level excluding the cost of centring , shuttering finishing in 1:2:4 (1 cement : 2 coarse sand : 4 coarse sand 20 mm nominal sizes)	0.50	cum	6450.00	3225.00/
4.	Earth work in excavation by mechanical means/ manual means over areas (exceeding 30 cm in depth 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth lead up to 50 m lift up to 1.5 m ,disposed earth to be leveled and neatly dressed in all kind of soil.	1.00	cum	155.60	156.0/-

Estimated cost based on DSR- 2014 CPWD :-

Rs.32,293/-

CONDITIONS: - AS ENCLOSED




CONDITIONS

1. Work will be executed as per schedule and direction of engineer in charge.
2. 1% water/electric charges will be recovered from the gross amount of bill, if the work is executed within DMS premises.
3. Rate so quoted will be valid up to March 2018.
4. The work will be executed as and when asked for which a separate work order will be issued on the basis of approved rate term and conditions.
5. No any escalation will be considered in respect of hike in prices of labour and materials till the rate is valid.
6. No any extra payment will be made for any hidden item
7. GST will be paid extra as per rules
8. Work will be executed within 20 days after issue of work order failing which a penalty of Rs. 100/per day will be deducted from the bill till the completion of work and burning of wild growth/ grass will not be allowed in premises.
9. Earnest money of Rs. 646/- in the shape of DAC in favors of General Manager ,DMS of a scheduled bank to be deposited , without earnest money quotations will not be considered . Rate may be quoted with all inclusive of services tax and govt.tax etc.

Signature of contractor _____

Name and address _____



Assistant Engineer (Civil)