

SUBJECT :- Repair/replacement of damaged kota stone slabs/mandana in by product
Section in C.D., DMS During 2009-10

Sealed quotation are invited for the above mentioned work from working / willing contractors and same shall be received up to 3.0 PM and shall be opened at 3.30 PM on 31-10-2009 in the office of AE (C) R.NO. 43 Admn block in the presence of intending contractors. Contractors should satisfy them selves with the scope of work before quoting the rates. Quotationers are requested to put the same in the tender box kept in the office of AE (Civil) Room NO. 43.

SCHEDULE OF WORK

S.NO.	Description of Items	Qty	Rate	Unit	Amount
1	Dismantling tile work in floors and roof laid in cement mortar including stacking material within 50 mlead for thickness of tile 10mm to 25 mm	50.00	10.90	sqm	545.00
2	Dismantling stone slab flooring laid in cement mortar including stacking of service able material and disposal of unserviceable material within 50 mlead	50.00	40.50	sqm	2025.00
3	Providing and laying ist quality ceramic glazed wall tile confirming to IS-15622 of approved make in all colors, shades of any size as approved by engineer in charge in skirting, risers of steps and dados over 12mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm including pointing in white cement mixed with pigment of matching shade complete	50.00	556.6	sqm	27830.00
4	Kota stone slabs flooring over 20mm average thick base over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4(1 cement : 4 coarse sand) 25 mm thick	50.00	694.40	sqm	34720.00

- 5 Providing and fixing mandana stone slabs flooring over with 25mm to 40 mm thick dressed mandana stone hand cut/ machine cut fixing 50mm thick base of cement mortar 1:3(half part cement, half part acid proof powder and 3 parts coarse sand including foxing same in line and level with a specific groove of 12 mm all along including filling the joints with acid proof cement mortar, with grinding, polishing etc. complete as directed by engineer in charge.

10.00 780.00 sqm 7800.00

- 6 Removal / building rubbish of malba from DMS premises to be dumped from within 10 km from dms premises by mechanically/ manually including loading and unloading as per direction of engineer in charge

10.00 84.54 cum 845.00

Estimated Cost Rs 73,765.00

CONDITIONS :- AS ENCLOSED



CONDITIONS

1. Work will be executed as per direction of engineer in charge.
2. 1% water/electric charges will be recovered from the gross amount of bill, if the work is executed within DMS premises.
3. Rate so quoted will be valid up to March 2010.
4. The work will be executed as and when asked for which a separate work order will be issued on the basis of approved rate term and conditions.
5. No any escalation will be considered in respect of hike in prices of labour and materials till the rate is valid.
6. No any extra payment will be made for any hidden item
7. Work will be executed within 30 days after issue of work order failing which a penalty of Rs. 100/per day will be deducted from the bill till the completion of work.

Signature of contractor _____

Name and address _____


Assistant Engineer (civil)
विद्युत विभाग कोयला-110002
Milk Scheme - 110002